

DASNY GRANT

Electrical proposal to install outlets for five (5) Computers and IT lines relocated as follows:

Install five (5) Quad Surface Mounted Wire Mold Outlets along front wall where shelving is going to be removed.

- Install necessary 120 Volt Feeders for Basement Panel for new Outlets.

Note: Existing Outlets to be left in place for other Computers.

Run existing Cat 5 IT Cables for Computers.

- IT Outlet to be on surface in Wire Mold and RJ-45 Jacks.

Note: install RJ-45 Jacks and Crimp ons for IT pull in.

Note: The Library may need IT Person for Final Connections.

Inspection Fee and Port Jervis Building Permit included

RE: 6 Floor Outlets Installed

Electrical Proposal To Supply and Install (6) Flush Floor Outlets as Follows:

1. Floor Outlets

- Install (4) Flush Floor Outlets (1) For Each Table

- Install (2) Flush Floor Outlets for (3) Chairs In Front of the Fireplace

- Run Additional Feeder To Basement Panel for Above Floor Outlets

All work to be done in a good workmanlike manner and in accordance to the National Electrical Code